
Natural Refrigerants in Action: R744 Heat Pumps for HVAC & Refrigeration


ET Summit

September 17, 1:00 – 2:00pm



© The Regents of the University of California, Lawrence Berkeley National Laboratory

The path to ultra low-GWP refrigerants



The path to ultra low-GWP refrigerants



Funding

Incentives,
Rebates, Grants

Evidence + Resources

Real projects, and
industry resources to
replicate + scale

Transition to
ultra-low GWP
refrigerants

ANSWR

CO₂ Heat Pump


Air-to-Water and Water-to-Water

HVAC Heating + Cooling, Simultaneous Heating + Cooling, DHW Production, Hot Water Boiler

Nominal Sizes: 20, 60, 90, 120 Tons


20TR Model

(fits through door and elevator)



20 Ton model used for FLEXLAB, 60 Ton for Straus

Heat Pump(s)



Gas Cooler(s)


V-Bank



Horizontal



Vertical




Modules are designed for parallel installation

Flow

Why Flow Environmental Systems?

Strong potential for impact...

- Low-GWP, natural refrigerant (CO₂)
- Performance factors
 - High delivery temp (up to 180F)
 - Cold climate performance (down to -40F)
 - Efficient - high COP, no defrost
- Strong retrofit option
 - Simplified system design + install



ANSWR

CO₂ Heat Pump

Webpage:



Two CO₂ Heat Pump Demonstrations



HVAC in Large Commercial Buildings FLEXLAB – Berkeley, CA

- *Simultaneous Heating/Cooling/HW*
- *Advanced HVAC Controls*
- *Model Predictive Grid Response*



Commercial Cold Storage Straus Family Creamery – Rohnert Park, CA

- *Multiple Facility Cold Rooms*
- *Advanced Defrost Controls*
- *Model Predictive Grid Response*

Heat Pump Demo: Large Commercial HVAC


Goal: Demonstrate an advanced heat pump system that uses ultra-low GWP refrigerant, reduce high first costs, and improve efficient, dynamic operations.

Demonstration Site: Department of Energy's FLEXLAB® testing facility in Berkeley, CA



Technology: 20-ton ANSWR system, demonstrating simultaneous heating, cooling & DHW


M&V: Independently verified performance by LBNL

Industry Engagement: Testing results, modeling work & products, ANSWR performance factors, DMG Training Program



FLEXLAB Demonstration Configuration





Preliminary Results

Flow's heat pump performed within the target ranges for COP and % modulation

Performance Metric	Target Range	Results
COP (Cooling only)	3.0 - 6.2	2.0 - 4.2 (mean: 2.82)
COP (Heating only)	2.1 - 2.3	1.6 - 2.7 (mean: 2.01)
COP (DHW only)	3.0 - 6.4	2.0 - 4.2 (mean: 3.09)
COP (Simultaneously Heating, Cooling, DHW)	3.0 - 9.7	3.0 - 5.8 (mean: 4.30)
% Modulation of Load	0% – 100%	0% - 60%

Takeaways

- **Plug & play integration**
 - Flow HP easily replaces chiller + boiler
- **Simultaneous heating/cooling/DHW operations**
 - Significantly greater system efficiency compared to individual modes
 - Well-balanced thermal loads yield optimal performance
- **Acoustic Performance**
 - Heat pump unit: 60-65 dB at 1 meter distance vs Existing chiller: 75-80 dB at 1 meter distance
- **System Capacity Limitations**
 - Efficient FLEXLAB testbed design and mild spring weather conditions constrained testing capacity to below rated values
- **Operational Challenges**
 - Unit experienced downtime due to high pressure protection switch → converted to automatic reset

Heat Pump Demo: Commercial Cold Storage

Goal: Demonstrate an advanced heat pump system for commercial cold storage, reduce GHG emissions, save cost, improve energy efficiency and demand flexibility

Demonstration Site: Straus Family Creamery – multiple cold storage sites, -30F to +35F

Technology: 60-ton ANSWR system + thermal energy storage & advanced defrost controls

M&V: Independently verified performance by LBNL

Industry Engagement: Testing results, modeling work & products, ANSWR performance factors, DMG Training Program



Courtesy Straus Family Creamery

Connecting with the Industry



Design
Resources

*System specifications,
performance, modeling
results, etc.*

Case Study

*Summary of the
demonstration with
impacts (economic +
environmental)*

Workforce
Development

*DMG Training Center:
installation, operation
and maintenance of
CO2 heat pumps*

Stay Connected

Be the first to know about upcoming webinars, events, and industry resources, including DMG's upcoming Training Program.

Sign up for our newsletter with the QR Code!

Contact Information:

Carolyn Weisman (she/her), Project Manager
Carolyn.weisman@prospectsv.org



 ProspectSV | PATHWAYS

